



## CALIFORNIA DEPARTMENT OF TRANSPORTATION PLENARY SESSION

### Presented by:

Kevin Thompson, State Bridge Engineer  
Ray Wolfe, Supervising Bridge Engineer  
Michael Pope, Senior Bridge Engineer

### *California DOT Opening Remarks*

- **The “Big Picture” at California DOT:**
  - Department Organization.
  - Strategic Planning and Innovation.
  - Budget and funding for transportation needs.
- **Project Delivery:**
  - Project delivery in Caltrans.
    - Increase in funding
    - Shelf projects
  - Future Department project delivery will focus on congestion relief:
    - “Go California” legislation.
    - Accelerate design and construction schedules.
    - Continue development of relationships with partners in the delivery of transportation projects.

### *Innovative California Precast Applications*

- **San Mateo–Hayward Bridge (Widen):** The widening of the existing 4.9 mile long trestle portion of this vital San Francisco Bay crossing was designed with 90 % of the structure consisting of precast concrete fabricated structural elements. In summary, this widening consists of a thin cast-in-place deck poured on **precast** deck panels, supported by **precast** bulb-tee girders, that rest on **precast** bent cap shells, that are integral with **precast** octagonal piles.
  - Listed below is a summary of the precast components used in the San Mateo – Hayward Bridge Widening Project:





- 42 in diameter by 118 ft long precast concrete cylinder piles (total 826).
- Precast concrete bent cap shells (total 278).
- 42 in deep by 86 ft long precast, prestressed bulb-tee girders (total 2168).
- 3.25 in thick precast, prestressed concrete deck panels, (19,000 units, 893,500 sq ft total).
- Construction proceeded quite rapidly on this project. The width of the widening is 58.6 ft, and the contractor was able to build 3 – 90 ft long spans per week. This works out to the area of bridge deck equivalent to a football field constructed each week. This is considered one of the most successful precast projects ever constructed in California.
- This project will be presented in detail in the **Imagineering in California: San Francisco Bay Toll Bridge Projects** session. The presentation is titled: *San Mateo-Hayward Bridge Widening Project – Precast Intensive Design and Construction*, Ali Asnaashari, California DOT, Sacramento, Calif. and R. Jon Grafton, Pomeroy Corporation, Petaluma, Calif.
- **San Francisco–Oakland Bay Bridge (Skyway Project):** The new San Francisco–Oakland Bay bridge consists of two structure types: the self-anchored suspension portion spans over the main shipping channel, and the precast segmental (Skyway) portion that comprises a majority of the bridge.
  - Precast segments are cast in a temporary yard in Stockton, and shipped on barges to the job site in Oakland.
  - The Skyway consists of 452 individual precast segments, resulting in a total length of nearly 1.3 miles
  - The cost of the Skyway is \$1,042,000,000, and work is progressing on schedule.
  - To date, over 360 of the 452 segments have been cast, with an average production rate of 3 – 4 segments per week.





- To date, all of the Skyway piers are complete, and approximately 220 units have been erected and post-tensioned into place.
- This project will be presented in detail in the **Imagineering in California: San Francisco Bay Toll Bridge Projects** session. The presentation is titled: *San Francisco – Oakland Bay Bridge Skyway Project – Precast Segmental Fabrication and Construction*, David Neumann, California DOT, Sacramento, Calif.
- When completed, the new bridge is expected to look similar to the artist's rendering shown on the right side of the page.




- **Richmond–San Rafael Bridge Project:** The purpose of this project is to replace a deteriorated trestle section of the Richmond-San Rafael Bridge. Items that made this replacement unique include:

- The use of a single precast double-tee section with an overall width of 43'-8".
- The overall length of the replacement is 1.25 miles.
- Each girder is made up of three match-cast precast segments. These segments are assembled on a barge prior to shipping them from the plant to the job site.
- The center 40 ft segment is pretensioned, and the girder end segments have linear haunches.
- All three segments are post-tensioned together on the barge in order complete the 100 ft long simple span girder.
- Once in place, four simple span girders are post-tensioned together for continuity to create 400 ft long frames
- This project will be presented in detail in the **Imagineering in California: San Francisco Bay Toll Bridge Projects** session. The presentation is titled: *Richmond-San Rafael Bridge Project – Spliced Girder Case Study*, Tim Holien, Pomeroy Corporation, Petaluma Calif. and Craig Chatelain, DMJM + Harris, Sacramento, Calif.





- **San Mateo – Hayward Bridge (Retrofit):** Piers supporting the main spans of this bridge lacked the necessary lateral capacity to withstand bay area earthquake. The solution involved retrofitting the existing piers with two precast “dog-bones” post-tensioned together, and pin-connected to 4 large diameter piles designed to limit seismic displacement.
  - Project involved the seismic retrofit of 20 piers, resulting in 40 precast units.
  - Epoxy coated bar reinforcing steel was required throughout. Rebar cages were fabricated in the plant, and lifted onto barges for forming and pouring of concrete.
  - The rebar cage itself weighed 55 tons.
  - A completed “dog-bone” is 9 ft tall, 100 ft long, with a 24 ft maximum width. Casting was done on the barge, because the overall weight of one unit is 550 tons. The finished units were barged to the job site from Petaluma.
  - The units are placed directly above their final position, a wet splice is poured, then the units are post-tensioned, and released to rest on the pinned connections at the 4 pile locations.
  - This project won a PCI Award, and is considered one of the most innovative bridge applications of precast concrete in California.



## *California Standard Precast Girder Applications*


Back in the late 1950's and early 1960's, during a period that this country's Interstate transportation system was under development, prestressed concrete became a practical solution in the design and construction of bridges. Most of the country adopted the precast/prestressed concrete girder bridge as a preferred structure type, and these bridges have served the State DOT's well for almost 50 years.

During this same time frame, California took a slightly different path than the rest of the nation. For a variety of different reasons, California adopted the cast-in-place, post-tensioned box girder as its structure of choice. However, precast-pretensioned girder bridges have always had a place in California. In fact, recent statistics show an increasing percentage of bridges in California are being designed with precast girders, and with accelerated project delivery as a main focus within the Department, that trend is expected to continue well into the future.




- **California “I” Girder:** Developed as a standard girder shape in the late 1950’s, this structure type has several advantages:

- Used routinely for span lengths up to about 100 feet.
- Results in the elimination of ground-supported falsework, which allows for the following:
  - Enhanced safety to the traveling public.
  - Reduced fill cone heights.
  - Reduction in working days, resulting in less impact to traffic flow.
- Ideal for widenings because of limited long-term deflections once deck is poured (minimal impact to existing structure).
- Excellent quality control of girder fabrication.
- Many California fabricators are able to produce this girder, making this structure type competitive with cast-in-place structures in the 100 foot span range.



- **California “Bulb-tee” Girder:** Introduced as an alternative to the cast-in-place box girder about 8 years ago, this girder can be designed to span 180 ft or more. In addition to the benefits of the California “I” girder, the “Bulb tee” has the following characteristics:

- When pre-tensioned, this girder is used routinely for span lengths up to 125 feet, and depending on the haul route, as long as 140 feet.
- When girder segments are spliced together with post-tensioning, spans as high as 180 feet or more can be achieved.
- The girder section modulus makes it possible to design a debonded strand pattern to control tensile stresses at the top fiber of the girder end region.
- Specific applications of the California “Bulb-tee” girder will be presented in the **Imaging in California: Precast Bridge Applications** session. The two presentations are titled:




- *Sacramento River Bridge Replacement Project – Spliced Girder design and Construction*, Mark Darnall, California DOT, Sacramento, Calif.
- *California Long-Span Bulb-Tee Girder Construction*, Mike Hein, Con-Fab California Corporation, Lathrop, Calif.




- California “Bath-tub” Girder:** Introduced in California at the same time as the “bulb-tee”, the California “Bath-tub” girder isn’t nearly as popular as it’s relative. Some of the drawbacks are: cost, fabrication difficulty, cross-slope issues, form availability and hauling weight. However, use of the California “bath-tub” girder has the following benefits:

- Has a cast-in-place box girder appearance, which is useful in maintaining an aesthetic corridor theme.
- Like the “bulb-tee”, when girder segments are spliced together with post-tensioning, spans as high as 180 feet or more can be achieved.
- Girder segments can be cast well ahead of when they are needed at the bridge site. Girder segments can be erected quite rapidly, with minimal traffic impact.



- California Voided Slab:** Pre-engineered for span lengths up to 48 feet, these slab units are commonly used in California under the following conditions:

- Depth-to-span ratios of 0.03 make this girder a good choice for small spans, with limited temporary or permanent clearance requirements.
- In remote areas of the state Modoc, Siskiyou counties for example, where ready mix concrete is difficult to obtain.
- Used on small creek crossings where rapid construction is required.
- Again, as with all precast elements, voided slabs are fabricated with excellent quality control and assurance.



- Other Less Common Girder Shapes:**

- Precast trapezoidal girder (spliced and simply supported).
- Precast double-tee girder.
- Precast rectangular girders.